BRUHAT BANGALORE MAHANAGARA PALIKE

APPROVED SCHEDULE - B

Name of Work :Improvements to Size stone masonry (SSM) Drains from Amruthahalli Govt. School to Eshwara temple, Amruthalli in ward no. 07 Byataryanapura.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of KRIDL	
				In Figures	In Words
1	73.14	KSRRB M200-15.1: Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 meters complete as per specifications. Iii) dismantling stone masonry, a rubble stone masonry in lime mortar,	cum	200.88	Rupees Two Hundred and Eighty Eight Paise Only
2	99.90	KSRB 2-2.1 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, **in ordinary soil** not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications,	cum	151.74	Rupees One Hundred Fifty One and Seventy Four Paise Only
3	39.83	KSRB 4-1.2 : Providing and laying in position plain cement concrete of **mix M10 with OPC cement @ 220 Kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	4497.12	Rupees Four Thousand Four Hundred Ninety Seven and Twelve Paise Only
4	86.70	KSRB 5.2.3 : Providing and constructing granite / trap / basalt size stone masonry in **foundation with cement mortar 1:6**, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	cum	3549.96	Rupees Three Thousand Five Hundred Forty Nine and Ninety Six Paise Only
5	420.00	KSRB 15.1.3: Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	79.92	Rupees Seventy Nine and Ninety Two Paise Only
6	270.00	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications.	Sqm	224.64	Rupees Two Hundred Twenty Four and Sixty Four Paise Only
7	106.10	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams.	cum	6468.12	Rupees Six Thousand Four Hundred Sixty Eight and Twelve Paise Only

EXECUTIVE ENGINEER-2
KRIDL, BBMP, Bangalore

Executive Engineer
Byatarayanapura Division
Yalahanka Zone, B.B.M.P.
Bangalore-560092

8	148.59	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Qtl	7380.72	Rupees Seven Thousand Three Hundred Eighty and Seventy Two Paise Only
9	76.00	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km	cum	72.71	Rupees Seventy Two and Seventy One Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-2
KRIDL, BBMP, Bangalore

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92